



Light Weight FRP Decks for Bridges



Long Lasting
Lightweight
Accelerated Construction

Scott Reeve
Composite Advantage

20+ Years of Success and Lessons Learned

- First FRP bridge decks
 - Pedestrian bridge in Aberfeldy, Scotland (1992)
 - Vehicle bridge in Russell, Kansas (1996)
- FRP Federal and state agencies focused technology funds for FRP applications
 - Kick start
 - Evaluate, improve and disseminate information



Fiber Reinforced Polymer (FRP) Composite Benefits

- Light Weight
 - Only 20% of reinforced concrete panels
 - For vehicle decks, FRP is 20 psf; concrete is 100 psf
 - Valuable for movable bridges; truss bridges
 - Quick installation
- Prefabricated Bridge Elements
 - Accelerated construction
 - Incorporate features in shop fabrication
 - Lower cost; higher quality
- Long Lasting and Low Maintenance
 - Corrosion resistant to chemicals and water

Bridge Applications in U.S.

Composite Products
in the U.S.



Number

0
1
2
3
4
5
10
15
20
30



Vehicle Bridge Deck Installations

- Over 100 in US
- Largest is almost 19,000 sf
 - Haverhill, Massachusetts
 - Six spans; one is swing span
 - Prefabricated with crown; rail post connections; and expansion joints



Deck Panels with molded-in crown



Deck Panel Features



- Expansion Joints
 - Galvanized steel plates
 - At end of deck spans for impact resistance
 - Attached in the shop
 - Includes rail for neoprene seal



- Rail Posts
 - Attached to internal steel reinforcement

- Wear Surface
 - Polymer Concrete



- **Lightweight**
 - Efficient transportation; many panels per truck
 - Only need small equipment

- After steel is rehabilitated or replaced, the deck is connected






- Prefabricated panels are easy to install
- From one end to the other

- Quick installation
 - One to five days; not 28 days for concrete to cure



Design Flexibility and Prefabrication Benefits are evident in Swing Span end panels



Span 4


Swing Span 3

Installed Panels at Expansion Joint

- Upfront design work makes installation go faster and final structure is higher quality
- Coordinate with contractor for as-built dimensions and construction tolerance
- Account for temperature during installation



- Overlay is same as used on any bridge
 - Polymer concrete
 - Asphalt




FRP Market Fit

- NOW Value is
 - Installation savings using Prefabricated Bridge Elements
 - Light Weight
- Movable bridges
 - Deck weight has direct effect on mechanical equipment and operational costs
- Historic steel truss
 - Remove load ratings
 - Meet local community desires
- Steel grate replacement
 - Solid surface protects superstructure
 - Lower noise



Special Applications

- Light weight fairings to eliminate dynamic response under wind conditions
 - Sarah Long lift bridge between NH and Maine
 - 2017 installation
- Light weight ballistic protection of critical bridge elements (cables)



Floating Bridge

- FRP provides structural capability, corrosion resistance and flotation
- Brookfield, Vermont



Challenges

- Installations dropped off after Innovative Bridge Research funding ended
- Some failures
 - Certain suppliers (others have no issues)
 - Lessons learned have been incorporated
- Lack of standards
 - Harder for some agencies/designers to specify FRP
 - Need suppliers to prove qualification
 - Special provisions in specs are used to address this
- Price premium
- Most procurements are acquisition based
 - Slow movement to Life Cycle analysis

Pedestrian Bridges & Decks



- Long lasting
- Design flexibility in prefabricated product



Market Successes

- Structural capability accepted
- Accelerated construction
- Some customers buying for low maintenance and life cycle savings
- AASHTO Guide Specification in place



Design Flexibility: Functional Features in Prefabricated Product

Crown

**Drainage scupper
with grating**

Curbs

Railing Attachments

**Expansion joint cover plate and
curb cover**



Key Applications

- Signature bridges
- Rails to Trails
- Architectural designs (aesthetics, shapes, colors)
- Light weight for erection of fully assembled bridges



FRP Deck Enables Accelerated Construction of Truss Bridges



- Truss is fully assembled near highway
 - Steel, FRP deck, fencing
 - No deck installation over the road
- 57 deck panels installed in 1.5 days

FRP Deck Enables Accelerated Construction of Truss Bridges

- Spans towed to position on vehicle bridge
- Largest lift was 132,000 lb
 - Precast concrete would have added 74,000 lb
- Road closure of 15 minutes per span !



Cantilever Sidewalks



- Shared use paths
- Safe separation from traffic
- Lower cost than separate bridge



- Add or widen sidewalks
- No increase in dead load



Current Efforts

- Information Sharing
 - Case studies so owners and designers know how FRP can benefit their projects
 - FAST Act has provision for FHWA / TRB to report on IBRC results for FRP and other technologies
- Education
 - Presentations at conferences, agencies and design consultants, universities
- Finding proponents in many places
 - Architects: aesthetics
 - Designers: prefab carries out design best
 - Maintenance Departments – less work

FRP Bridge Decks

- Providing innovation and options
- Design flexibility of an engineered product
- Right market fit
 - Light weight
 - Prefabricated with design features
 - Accelerated construction
 - Very low maintenance
- Vehicle
 - Movable, Steel Truss, Specialty Solutions
- Pedestrian